MANUFACTURING & PROCESSING GUIDELINES

1. INTEGRATED PROCESSING WORKFLOW

All production facilities must strictly align processing steps according to the following structural checklist:

* Step 1: Fiber Dyeing & Yarn Spinning (Uniform yarn dye penetration)
* Step 2: High-Speed Weaving (Maintained on rapier/water-jet looms to ensure precise thread counts)
* Step 3: Printing Operations (Digital, Rotary Screen, or traditional block application)
* Step 4: Value-Addition (Custom multi-head embroidery, Zardosi work, or sequence placing)

2. TECHNICAL SPECIFICATIONS FOR APPAREL WEAVING

* Premium Cotton Fabrics: Must maintain a minimum of 160 Thread Count (TC) structures.
* Silk/Chiffon Weaves: Must run on low-tension settings to eliminate structural yarn pulling.
* Edge Selvedges: All printed fabric rolls must feature cleanly pinned, uniform edges stamped with the "Gokul Print" quality mark.

3. ENVIRONMENT, HEALTH & SAFETY (EHS) STANDARDS

* Effluent Treatment Plant (ETP) Compliance: 100% of water discarded from dyeing and washing loops must cycle through the internal primary, secondary, and tertiary treatment plants. Zero untreated wastewater discharge is permitted.
* Air & Energy Efficiency: Manufacturing machinery blocks must utilize the clean energy grids set up by corporate directives to minimize carbon footprint.
* Personal Protective Equipment (PPE):
  - Dyeing/Chemical House: Respirators, protective eyewear, and chemical-resistant gloves are mandatory.
  - Loom and Weaving Sheds: High-noise areas require industrial ear defenders at all times.